



# ESTIMATE

**Tidewater Home Improvement LLC**

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

## BILL TO

**Chris Conley**

Chris Conley

1406 Antoinette Cir

Hampton, VA 23663

United States

(757) 951-7924

skinscmc05@yahoo.com

**Estimate Number:** 1435

**Estimate Date:** September 30, 2026

**Valid Until:** October 7, 2026

**Grand Total (USD):** \$2,106.00

### Drywall Repair

1 \$756.00

Remove and replace the water-damaged drywall on the lower wall beneath the window and at the cutouts; hang, tape, mud, sand and prime.

### Subfloor Repair

1 \$700.00

Cut out and replace the water-damaged plywood subfloor at the sink and corner area with new material and blocking.

### Granite Countertop Remove & Reinstall

1 \$650.00

Remove, protect and store the existing granite countertop for the subfloor and wall access, then reset and re-seal it once the repair is complete.

**Grand Total (USD):**

**\$2,106.00**

## Notes / Terms

### JOB DESCRIPTION

Drywall Repair: remove and replace the water-damaged drywall on the lower wall beneath the window and at the cutouts; hang, tape, mud, sand and prime.

Subfloor Repair: cut out and replace the water-damaged plywood subfloor at the sink and corner area with new material and blocking.

Granite Countertop Remove & Reinstall: remove, protect and store the existing granite countertop for the subfloor and wall access, then reset and re-seal it once the repair is complete.

### FINDINGS & CAUSE OF LOSS

1. Water damage to the drywall, subfloor and countertop area at the kitchen sink wall resulting from a dishwasher overflow.

2. The damaged materials listed in this estimate were wet from that overflow and require replacement.

Conclusion: the damage described in this estimate was caused by a dishwasher overflow.

NOT INCLUDED: cabinet or countertop replacement; flooring installation; painting of the full room; mold, fungus or

for Estimate #1435

Page 1 of 2



---

disinfectant treatment; permits.

Notes:

\*\*Jobsite will be left clean once completed.

\*\*Contractor is not responsible for damage caused inside the home while repairing.

Warranty:

\*\*12 months workmanship on the project.

Payment Terms:

Total Project Cost: \$2,106.00

Deposit to Schedule: \$1,053.00

Final Payment: \$1,053.00

Check is a preferred method.

\*\*You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: valid until 10/07/2026.